



SHYAM LAL COLLEGE
(University of Delhi)
G.T. Road, Shahdara, Delhi-32
Website: www.shyamlal.du.ac.in

Ref./Slc./Dc/2017./.....

September 1, 2017

Sub: - Invitation of rates for Sewer line & Manhole Construction work.

Dear Sir

You are requested to submit to the college office (Day) your rates for above mentioned work (Work Specification attached) 4:30 pm on latest by, Wednesday, 6th September 2017.

Thanking you

Yours faithfully

Sanjay Kumar

Sh. Sanjay Kumar

Convenor

Development Committee, SLC (Day)

SCOPE OF WORK

01/09/2017

Shyam Lal College (University of Delhi), G.T Road Shahdara, Delhi-110032, Invites sealed quotations for Sewer Line & Manhole Construction Work in the college.

Followings are the Specifications.

S.N.	DESCRIPTION	QUANTITY (Approx.)	UNIT RS	AMOUNT
1.	<p>Sewer Line</p> <ol style="list-style-type: none"> PVC Pipe (6" dia, 6 kg/cm²) ISI Certified make Supreme, Prakash, Prince, used with plain cement concrete (1:2; 4) batching & covering. Minimum & maximum depth of pipe laying 300 mm to 1000 mm. Earth work excavation as per required depth, all type Cement concrete, brick work, dismantling, back filling compaction, cleaning, floor finishing & disposal of malaba all is completed as per direction of college committee /college authority. Slope of sewer line 1:25 (MH to MH) Including Connect the sewer line both side as per site requirements. 	50.00 Rmt.		
2.	<p>Manhole</p> <ol style="list-style-type: none"> 460X4460X500(as per required) Internal dimension. 115 mm thick brick work 1:4 mortar Internal & external Cement plaster with neat cement finishing coat. Heavy Duty RCC Cover with frame. PCC 1:3:6 Earth work excavation as per required depth, all type Cement concrete & brick work dismantling, back filling compaction, cleaning, finishing & disposal of malaba all is completed as per direction of college committee /college authority. (bricks provided by college only labour and mortar charges) 	10 Nos		
3.	<p>Flooring Work</p> <p>Providing & fixing 22 mm thick paver tile flooring with 20 mm thick mortar (1:4) bed should be used. Colour & design decided by college Authority.</p>	50 Sqmt		

GENERAL TERMS & CONDITIONS

- Rates are to be sent in sealed envelope from Bidders shall be addressed to the **Principal, Shyam Lal College** (University of Delhi), G.T. Road, Shahdara, Delhi-110032.
- No advance payment will be made.
- Date of Submission September 06, 2017 at 4:30 PM

- The work should be completed within **5 days** from the date of award of the Contract. College reserves the right to impose admissible penalty for the delay of work.
- In case of delayed completion, Penalty at the rate 1% per Day subject to a maximum of 10% of the value of the work shall be levied.
- In case of inordinate delay, the College is authorized to cancel the order and allot the work to the next lowest eligible agency at the risk and cost of the defaulting tenderer.
- If any additional charges related to taxes should be mentioned separately or otherwise the total amount will be treated as all inclusive.
- College reserves the right to accept or reject any or all the Quotations in full or part without assigning any reason. The decision of the college in this regard shall be final and binding on all. It shall not be obligatory on the part of the College to accept the lowest Quotations and no explanation shall be given with regard to reason for rejection of tender of any vendor.
- The work will be done as per the on-site instruction under the supervision of college Committee Members/college authority.
- Final bill will be paid as per the actual measurement.
- The payment will be done after the satisfactory approval given by the committee members/college authority.
- Any quarry or discrepancy clarifies by the committee members /college authority.
- All material should be use Govt. approved standard & first class quality.
- Extra remaining dispose material will be shift as per direction of a college committee/ college authority
- The quantity is approximate so 10% quantity is increase and decrease as per requirements.

**SEAL WITH SIGNATURE
(Contractor)**